

**Cobra Ridge Vents
Are The #1 Choice Of
Professional Builders
& Remodelers!**

Source: 2001 Builder Magazine Brand Use Study &
2001 Remodeling Magazine Brand Use Study



LTD. WARRANTY
40
YEARS

**Protects
Over
1,000,000
Homes!**

Ridge Vents (Exhaust)

Ridge Vents are your best overall value in attic ventilation.
They feature low installed cost with superior performance—
and they won't detract from the finished appearance of your roof!



Homeowner's Best Choice

- **Vents Your Attic...** Allows heat & condensation to escape at the most effective location — the ridge
- **Looks Terrific...** 100% shingle-over design is virtually invisible when installed
- **Superior Protection...** Helps to prevent wood rot and extend the life of your exterior paint
- **Safeguards Possessions...** Helps limit mildew growth caused by damp attic air
- **Energy Efficient...** May even reduce your energy bills!
- **Safer...** Helps prevent problems with insects, birds, and animals in your attic
- **Peace Of Mind...** Backed by a 40-year ltd. warranty*

*See ltd. warranty for complete coverage and restrictions

Professional's Best Choice

- **Greater Homeowner Satisfaction...** Low-profile design is hidden by ridge cap shingle
- **Easy To Install...** Quick 3-step process; no need for complicated fitting, wrapping, connectors, or end plugs
- **Nails Included...** Includes Smart Nails™ for reliable hand installation or 1 3/4" coil nails for nail gun installation
- **Superior Performance...** Provides 16.9 sq. in./linear foot (hand nail) or 14.1 sq. in./linear foot (nail gun) of net free ventilating area at the most effective location on the roof
- **More Reliable...** Will not crack or dent during shipping and installation; won't corrode, rust or turn brittle
- **Hip & Ridge Compatible...** Works with traditional sizes(11 1/2" x 12")

One 20' Coil of
Cobra Ridge Vent
replaces:



BOCA
See BOCA Evaluation Services, Inc.
Research Report #93-49-01
DADE COUNTY
Approval # NOA 00-0609.03

Texas Department
of Insurance
(C.R.V.II only) Product Evaluation RV-19
Listed (C.R.V.II only)
(See ICBO ES ER-5477)

**CCMC
Listed**
(C.R.V.II only)
See Evaluation Report
13000-R

Model No.	Size	
2017	20' x 8"	(nail gun version)
2008	20' x 8"	(hand nail version)
2005	20' x 10.5"	(nail gun version)
2000	20' x 10.5"	(hand nail version)
2058	50' x 8"	(hand nail version)
2050	50' x 10.5"	(hand nail version)
2016	50' x 10.5"	(nail gun version)

NOTE: Cobra products only available through your roofing sales representative

How Much Do I Need?

TOTAL ATTIC SQUARE FOOTAGE	RECOMMENDED LENGTH OF COBRA RIDGE VENT (FEET)*	MINIMUM INTAKE VENTILATION (NET FREE AREA IN SQ. IN.)
1600	23/27	384
1900	27/32	528
2200	32/38	500
2500	36/43	600
2800	40/48	672
3100	45/53	744
3400	49/58	816

*First figure pertains to Hand Nail, second figure pertains to Nail Gun



Texas Department
of Insurance
Product Evaluation RV-17
DADE COUNTY
Approval # NOA 99-0422.04

10' ALUMINUM RIDGE VENTS

- **Quality-built...**For long life on the roof
- **Superior Performance...**Wide, free-flow drainage areas
- **Easy Installation...**Aluminum sections with pre-punched nail holes install quickly with strap and end/connector plug accessories
- **Watertight...**Built-in weather baffle prevents moisture infiltration

How Much Do I Need?

TOTAL ATTIC SQUARE FOOTAGE	RECOMMENDED LENGTH OF AR-10 METAL RIDGE VENT IN SQ. IN.	MINIMUM INTAKE VENTILATION (NET FREE AREA IN SQ. IN.)
1600	18	384
1900	22	456
2200	25	528
2500	28	600
2800	32	672
3100	35	744
3400	38	816

Mill Finish	Black	Brown	Weath.Wood	White	Gray	Description	Roof Pitch Range	NFA (sq.in.)
AR10	AR10BL	AR10BR	AR10WW	AR10W	AR10G	10' Ridge Vent (Std.)	3/12 - 8/12	215
AR10H	AR10BLH	AR10BRH	AR10WWH	AR10WH	AR10GH	10' Ridge Vent (Heavy)	3/12 - 8/12	215
ARS	ARSBL	ARSBR	ARSWW	ARSW	ARSG	Joint Straps		

ARCP

End /Connector Plugs

Cobra® (For warmer climates) RIGID VENT II™ EXHAUST VENT FOR ROOF RIDGE

Cobra® (For harsh winter climates) SnowCountry™ RIGID EXHAUST VENT FOR ROOF RIDGE

LTD. WARRANTY
40
YEARS


Homeowner's Best Choice

- **Vents The Attic...** Allows heat and condensation to escape at the most effective location—the ridge
- **Looks Terrific...** Shingle-over design blends into the ridge line
- **Watertight...** Passes the 110 mph-wind driven rain test*
- **Snow Guard...** Prevents snow infiltration in harsh winter climates (Snow Country™ only)
- **Insect Guard...** Specially designed 1/8" louver spacing helps to keep insects out
- **Energy Efficient...** May even reduce your energy bills!
- **Durable...** Designed with high-impact polymers
- **Peace Of Mind...** Backed by a 40-year ltd. warranty**
- **Colors To Match Your Shingles...** Available in black, brown, gray and weathered wood

* Under controlled laboratory conditions ** See ltd. warranty for complete coverage and restrictions

Professional's Best Choice

- **Fits Better...** Flexible 3-point hinge allows installation on 3:12 to 12:12 sloped roofs
- **Quick Alignment...** Special tabs allow for easy, reliable connection
- **No Overdrive...** Nail holes are reinforced
- **No End Caps Needed!**
- **Less Callbacks...** External baffles help deflect wind and rain
- **No Gaps...** Edge overhang allows smooth, continuous coverage between sections
- **Crush-Resistant...** Internal structural support for added durability
- **Effective...** Provides 18.5 sq. in. per linear foot of net free ventilating area
- **Hip & Ridge Compatible...** Works with traditional sizes (11 1/2" x 12")



How Much Do I Need?

TOTAL ATTIC SQUARE FOOTAGE	RECOMMENDED LENGTH OF COBRA RVII or Snow Country (FT)	MINIMUM INTAKE VENTILATION (NET FREE AREA IN SQ. IN.)
1600	21	384
1900	25	456
2200	29	528
2500	33	600
2800	37	672
3100	41	744
3400	45	816

One box (48") of Cobra Snow Country Rigid Exhaust Vent for Roof Ridge replaces:

18 Conventional Roof Vents

OR Ten 12" Turbine Roof Vents

Model No.	Color
2013 (RVII)	Black
2013-133 (RVII)	Brown
2013-345 (RVII)	Gray
2013-900 (RVII)	Weathered Wood
2061 (Snow Country)	Black

NOTE: Cobra products only available through your roofing sales representative



DADE COUNTY Approval # NOA 00-0809.03

Texas Department of Insurance – Product Evaluation RV-19 (C.R.V. II only)

BOCA See BOCA Evaluation Services, Inc. Research Report #93.49.D1

ICBO ES Listed See ICBO ES ER 5477



Made from over 90% recycled fiber; over 30% post-consumer content

CMC See Evaluation Report #12061-R

SHINGLE-OVER RIDGE VENTS

How Much Do I Need?

TOTAL ATTIC SQUARE FOOTAGE	RECOMMENDED LENGTH OF SRR4 RIDGE VENT (FEET)	MINIMUM INTAKE VENTILATION (NET FREE AREA IN SQ. IN.)
1600	26	384
1900	30	456
2200	35	528
2500	40	600
2800	45	672
3100	50	744
3400	54	816

- **Looks Great...** Low profile allows system to blend with roof lines
- **Durable...** Made from high-impact resin with UV stabilizers
- **Heat And Cold Resistant...** Tested from -76°F to 180°F
- **Effective...** 15 sq. in. net free area per lineal foot
- **Easier Installation...** Nail line for better alignment
- **Superior Performance...** Baffles prevent moisture from entering ridge
- **Strong...** Built-in strength to withstand exterior load



Model No.	Description	Roof Pitch Range	NFA (Sq. In.)
SRR4	4' Shingle-Over Ridge Vent	3/12 - 12/12	60
SRREP	End Plugs (Pkg. of 4)	–	–
BSRREP	Bulk Packed End Plugs	–	–

